



1. CONCRETE TO HAVE A BREAKING STRENGTH OF 3000 P.S.I. AFTER 28 DAYS.
2. EXPANSION JOINTS
  - A. TO BE PROVIDED:
    - 1) AT EACH POINT OF TANGENCY OF THE CURB.
    - 2) AT EACH COLD JOINT.
    - 3) AT EACH SIDE OF INLET STRUCTURES.
    - 4) AT EACH END OF DRIVEWAYS.
    - 5) AT LOCATIONS NECESSARY TO LIMIT SPACING TO 45 FEET.
  - B. MATERIAL TO BE PRE-MOLDED, ASPHALT IMPREGNATED, NON-EXTRUDING, WITH A THICKNESS OF 1/2 INCH.
3. CONTRACTION JOINTS
  - A. SPACING TO BE NOT MORE THAN 15 FEET.
  - B. THE DEPTH OF JOINT SHALL BE AT LEAST 1 1/2 INCHES.
4. BASE ROCK-2"-0 OR 3/4"-0, 95% COMPACTION. BASE ROCK SHALL BE TO SUBGRADE OF STEEL STRUCTURE OR 4" IN DEPTH, WHICHEVER IS GREATER.
5. DRAINAGE BLOCKOUT- 3" DIAMETER SCH 40 PVC OR ABS PIPE.
  - A. I.D. PIPE WITH COUPLING
  - B. DRAINAGE ACCESS THROUGH EXISTING CURBS SHALL BE CORE DRILLED OR CURB SAW CUT VERTICALLY 18" EACH SIDE OF DRAIN AND REPOURED TO FULL DEPTH OF CURB.

EMERGENCY MOUNTABLE  
P.C.C. CURB AND GUTTER

ENGINEERING  
DEPARTMENT  
1924 COUNCIL STREET  
P.O. BOX 326  
FOREST GROVE, OR 97116

city of  
forest  
grove