



1. CONCRETE TO HAVE A BREAKING STRENGTH OF 3000 P.S.I. AFTER 28 DAYS.
2. EXPANSION JOINTS
 - A. TO BE PROVIDED:
 - 1) AT EACH POINT OF TANGENCY OF THE CURB.
 - 2) AT EACH COLD JOINT.
 - 3) AT EACH SIDE OF INLET STRUCTURES.
 - 4) AT EACH END OF DRIVEWAYS.
 - 5) AT LOCATIONS NECESSARY TO LIMIT SPACING TO 45 FEET.
 - B. MATERIAL TO BE PRE-MOLDED, ASPHALT IMPREGNATED, NON-EXTRUDING, WITH A THICKNESS OF 1/2 INCH.
3. CONTRACTION JOINTS
 - A. SPACING TO BE NOT MORE THAN 15 FEET.
 - B. THE DEPTH OF JOINT SHALL BE AT LEAST 1 1/2 INCHES.
4. BASE ROCK-2"-0 OR 3/4"-0, 95% COMPACTION. BASE ROCK SHALL BE TO SUBGRADE OF STEEL STRUCTURE OR 4" IN DEPTH, WHICHEVER IS GREATER.
5. DRAINAGE BLOCKOUT- 3" DIAMETER SCH 40 PVC OR ABS PIPE.
 - A. I.D. PIPE WITH COUPLING
 - B. DRAINAGE ACCESS THROUGH EXISTING CURBS SHALL BE CORE DRILLED OR CURB SAW CUT VERTICALLY 18" EACH SIDE OF DRAIN AND REPOURED TO FULL DEPTH OF CURB.

**EMERGENCY MOUNTABLE
P.C.C. CURB AND GUTTER**

**ENGINEERING
DEPARTMENT**
1924 COUNCIL STREET
P.O. BOX 326
FOREST GROVE, OR 97116

**city of
forest
grove**