

- 2. MOUNT GFI RECEPTACLE 6" BELOW CEILING OF VAULT UNLESS LOCATED OTHERWISE BY NATIONAL AND/OR LOCAL ELECTRIC CODES. (GFI RECEPTACLE NOT SHOWN).
- 3. GFI RECEPTACLE SHALL BE LOCATED SO THE SUMP PUMP ELECTRICAL CORD WILL PLUG DIRECTLY INTO IT.



SUMP PUMP INSTALLATION

ENGINEERING DEPARTMENT 1924 COUNCIL STREET P.O. BOX 326

STD. DRG. NO 417

> SCALE NONE

H:\STANDARD DETAILS\WATER\3 INCH WATER METER VAULT-SUMP PUMP.DWG

LAST REV. 06/07/21